SECTION 08 3100

ACCESS DOORS AND PANELS

LANL MASTER SPECIFICATION

When editing to suit project, author shall add job-specific requirements and delete only those portions that in no way apply to the activity (e.g., a component that does not apply). To seek a variance from applicable requirements, contact the ESM Architectural POC.

When assembling a specification package, include applicable specifications from all Divisions, especially Division 1, General Requirements.

Delete information within "stars" during editing.

Specification developed for ML-3 projects. For ML-1 / ML-2, additional requirements and QA reviews are required.

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Ceiling and wall mounted, non-rated access door and frame units.

1.2 SUBMITTALS

- A. Submit the following in accordance with the requirements of Section 01 3300, Submittal Procedures:
 - 1. Catalog data which includes sizes, types, finishes, and details of adjoining work.
 - 2. Manufacturer's Installation Instructions and rough-in dimensions.
 - 3. Schedule: Types, locations, sizes, latching or locking provisions, and other data pertinent to installation.

PART 2 PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS

- A. Cesco Products
- B. J. L. Industries
- C. Milcor

Project I.D. [____] Rev. 1, September 28, 2006

2.2 FABRICATION

- A. Fabricate frames and flanges of 16 gauge steel.
- B. Fabricate door panels of 20 gauge steel with integral non-combustible insulation filler.

******* Or ******

- C. Fabricate door panels of 14 gauge steel (non-insulated)]
- D. Weld, fill, and grind joints to assure flush and square unit.
- E. Hardware:
 - 1. Hinge: 175 degree steel hinges with removable pins.
 - 2. Lock: Screw driver slot for quarter turn cam lock.

2.3 FINISHES

- A. Base Metal Protection: Prime coat units with baked on primer.
- B. Finish: Two coats acrylic enamel, white color or match adjoining color where exposed.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that rough openings are correctly sized and located.

3.2 INSTALLATION

- A. Install units in accordance with manufacturer's instructions.
- B. Install frames plumb and level in openings. Secure rigidly in place.
- C. Position unit to provide convenient access to concealed work requiring access.

FOR LANL USE ONLY

This project specification is based on LANL Master Specification 08 3100 Rev. 1, dated September 28, 2006.