SECTION 13074

PRESSURE RELIEF WALL PANELS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Pressure relief panels, frames, and attachment hardware for exterior walls of building spaces containing High Explosives operations.

1.2 PERFORMANCE CRITERIA

- A. Design loads
 - 1. Wind load 30 psf.
 - 2. Explosion load (from inside building) 20 psf.
- B. Equip each hinged panel with a restraint/holdopen mechanism designed to cushion the panel's deceleration as the full open position is reached, and to minimize the development of a vacuum in the enclosed area when the heated gases cool.
- C. Design system to accommodate movement of components without buckling, failure of joint seals, undue stress on fasteners, or other detrimental effects when subjected to seasonal temperature ranges.
- D. Design system to accommodate tolerances of structure.
- E. Provide positive drainage to exterior for moisture entering or condensate occurring within the panel system.
- F. Design panel system to allow for manual resetting of panels after release.

1.3 SUBMITTALS

- A. Submit the following submittals in accordance with the requirements of Section 01300.
 - 1. Catalog data indicating panel components and construction, restraint mechanism, and mounting hardware.
 - 2. Manufacturer's installation instructions.
 - 3. Samples of manufacturer's standard range of colors for selection.
 - 4. Shop drawings indicating dimensions, panel layout, construction details, method of anchorage, method and sequence of installation.
 - 5. Test reports from testing at completion of installation.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Conspec Systems, Inc., Explovent system
- B. Construction Specialties, Ltd., Explovent system

2.2 MATERIALS

- A. For panels use 0.032 inch thick 3003 or 5005 stucco finish aluminum alloy sheet with Kynar 500 finish.
- B. Use 2 inch thick rigid foam insulation with flame/smoke rating of 25/450 in accordance with ASTM E84. Insulating value of panels must be R14 minimum.
- C. For exterior gasketing material use wool pile, fiber type, with continuous polypropylene center fin. For interior gasketing material use open cell foam with a polyethylene liner.
- D. For frame use 0.063 inch thick 6063-T52 alloy extruded aluminum with Kynar 500 finish to match panels.
- E. Use fasteners made of aluminum or stainless steel.

2.3 FABRICATION

- A. Form panels by laminating sheets of aluminum to each face of 2 inch thick foam insulation cores
- B. Install panels in extruded aluminum frames with perimeter gasketing. Hinge panels at top edges, to swing out.
- C. Install calibrated release mechanisms that allow panels to open at specified internal pressure.
- D. Install holdopen devices that prevent panels from closing when opened by explosion. Panels shall close automatically if opened by wind driven activation.
- E. Install retrieval devices that allow manual retrieval of opened panels.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Install panel assemblies in accordance with approved shop drawings and manufacturer's installation instructions.
- B. Protect metal surfaces in contact with cementitious materials with 1 coat of bituminous paint. Allow paint to dry before installation.
- Permanently attach frames to structure; aligned level and plumb to manufacturer's tolerances.

3.2 TESTING

A. When installation is complete, test each panel for operation at specified pressures and submit test reports to Contract Administrator.

END OF SECTION