V= verify W = witness

This table clarifies the assigned duties and responsibilities for new construction and significant modification inspections associated with the IBC, IEBC, NFPA, DOE O 420.1C, and the LANL ESM. This table represents the minimum expectations; additional witnessing and observation can be performed by either party indicated as desired.

BI = IBC Inspector (LBO) - **FP** – Fire Protection Inspector (FPO) **EI** = Electrical Inspector (OSHISH) - **STUP** = Start-Up & Commissioning (LANL)

 \underline{V} = Verify: The act of checking by an independent qualified person that an installed SSC, feature, test result, or process conforms to established criteria. In this context this would typically be performed by review of test documents, installation records, or other supporting information required to be generated by the Project.

 \underline{W} = Witness: The act of on-site observing by an independent qualified person an installation and/or testing of an SSC, feature, or process to verify conformance with established criteria. In this context it would require physical presence and visual observation of the activity while it is taking place. If a physical presence is not possible or safe, alternative means can be used if feasible and approved.

V or V/W INSPECTION	BI/EI Insp.	FP
------------------------	----------------	----

	Fire Protection Water Supply Systems					
v	V 1. Underground piping materials, size and routing per design documents B		BI			
V	V 2. Restraint methods (thrust blocks, retaining fittings) per design documents		BI			
		Appurtenances (hydrants, valves, etc.) and locations per design documents				
v	3.	During installation:	BI			
		At final:		FP		
w	4.	Hydrostatic (leak) testing of piping	BI			
V/W	5.	Flushing of underground piping	BI			
V/W	6.	Hydrant flushing, dry barrel drainage, and fire flow verification	BI			
v	7.	Backfill and compaction methods per design documents	BI			
v	8.	Review/Approve Contractor's Material and Test Certificate		FP		

Fire Sprinkler System Installation

v	1.	Pipe materials, routing, and size per design documents BI		
v	2.	Piping is properly supported per design documents BI		
v	3.	Piping is properly braced (seismic restraints installed per design documents)	Piping is properly braced (seismic restraints installed per design documents) BI	
v	4.	Anchor bolt installations for supports per design documents	BI	
V/W	5.	Hydrostatic (leak) test of piping	BI	
V/W	6.	Pneumatic (leak) test of Dry Pipe system BI		
V/W	7.	Flushing of underground piping connections BI		
v	8.	Proper clearances between piping and adjacent commodities BI		
v	9.	Sprinkler heads are properly installed (type, orifice size, orientation, coverage, temperature rating, etc.) During installation: At final:	n: BI	

V or V/W	INSPECTION			FP
		Flow testing (alarm testing) of system piping		
V/W	10.	During installation:	BI	
		At final:		FP
v	11.	Proper installation of system components (valves, alarm valves, trim, alarm devices, supervisory air, backflow prevention, drains, gauges and other appurtenances) per design documents		
		During installation:	BI	
		At final:		FP
		Proper signage, labels and flow arrows on piping and components		
V	12.	During installation:	BI	
		At final:		FP
v	13.	Proper methods for freeze protection (anti-freeze loops, dry and preaction configurations, etc.)		FP
V/W	14.	Backflow prevention device(s) forward flow and back flow testing and certification (IAW O&M 406)	BI	
V	15.	5. Review/Approve Contractor's Material and Test Certificate		FP
	Fire	Pump Installation		
V	1.	Pipe materials, routing, and size per design documents	BI	
V	2.	Piping is properly supported per design documents	BI	
V	3.	Piping is properly braced (seismic restraints installed per design documents)	BI	
v	4.	Anchor bolt installations for supports per design documents	BI	
V/W	5.	Hydrostatic (leak) test of piping	BI	
V/W	6.	Flushing of suction piping connections	BI	
v	7.	Proper clearances between piping and adjacent commodities	BI	
v	8.	Field installed normal AC power wiring conforms to NFPA 70	EI	
v	9.	Field installed fire alarm wiring conforms to NFPA 72		
		Pump appurtenances are properly installed per design documents		
v	10.	During installation:	BI	
		At final:		FP
		Flow testing of fire pump, comparison to shop curve		
V/W	11.	During installation:	BI	
		At final:		FP
		Proper signage, labels and flow arrows on piping and components		
v	12.	During installation:	BI	
		At final:		FP

V or V/W	INSPECTION			FP
		Fire Alarm testing of system devices		
V/W	13.	During installation:	BI	
		At final:		FP
		Sequence of operation testing of system		
V/W	14.	During installation:	BI	
		At final:		FP
V/W	15.	Testing of pump engine / motor		FP
v/w	16.	Backflow prevention device(s) forward flow and back flow testing and certification (IAW O&M 406)	BI	
V	17.	Review/Approve Contractor's Material and Test Certificate		FP
	Fire	Detection and Alarm Systems		
v	1.	Proper routing of FA (fire alarm) conduit, raceway, etc.	BI	
v	2.	Proper support of FA conduit, raceway, etc.	EI	
		System components are installed in proper locations and at proper heights		
v	3.	per design documents		
v	5.	During installation:	BI	
		At final:		FP
V	4.	FA conductors/cabling installed per design documents	BI	
V	5.	Proper voltage of FA conductors	BI	
V	6.	Field installed normal AC power wiring conforms to NFPA 70	EI	
V	7.	Field installed FA wiring conforms to NFPA 72	BI	
v	8.	Wiring and termination to control panels and field devices are properly routed and landed per design documents		
V	9.	Continuity and/or meggar testing of conductors/cable	BI	
		Proper functionality of fire alarm system devices		
w	10.	During installation:	BI	
		At final:		FP
		Size and type of batteries per design documents (and calculations)		-
v	11.			
v	11.	During installation:	BI	
		At final:		FP
W	12.	Proper functionality of fire alarm system logic and control functions per design documents		FP
w	13.	Proper fire alarm system control logic, including auxiliary functions per design documents		FP
w	14.	Proper remote reporting to CAS		FP

V or V/W	W INSPECTION		BI/EI Insp.	FP
v			EI	FP
V	16.	Review/Approve NFPA 72 Record of Completion		FP
		Special Extinguishing Systems		
V	1.	Pipe routing and size per design documents	BI	
V	2.	Piping is properly supported per design documents	BI	
V	3.	Piping is properly braced (seismic restraints installed per design documents)	BI	
v	4.	Anchor bolt installations for supports per design documents	BI	
V/W	5.	Hydrostatic/ Pneumatic (leak) test of piping	BI	
V	6.	Proper clearances between piping and adjacent commodities	BI	
v	7.	Discharge nozzles are properly installed (type, orifice size, orientation, coverage, obstructions, etc.) During installation: At final:	BI	FP
v/w	8.	System actuation and alarm testing During installation: At final:	BI	FP
v	9.	Proper installation of system components (valves, agent storage containers, alarm devices, supervisory devices, gauges and other appurtenances) per		FP
v	10.	Proper signage, labels and flow arrows on piping and components During installation: At final:	BI	FP
v	11.	Proper functionality of control system logic and control functions, releasing panel, auxiliary functions (fan shutdown, power shunt-trip, door closure, damper closure, pre-discharge alarms, abort stations, etc.) per design documents		FP
v	12.	Review/Approve Contractor's Material and Test Certificate		FP

V or V/W		INSPECTION	BI/EI Insp.	FP
	Build	ding Construction Features, Walls/Barriers		
v	1.	Fire-rated floor and roof systems are constructed per design documents	BI	
V	2. Roof systems/covering assemblies are installed per design documents BI		BI	
V	3. Fire-rated walls/barriers constructed per design documents BI		BI	
V	4.	Fire-rated walls/barriers labeled/stenciled with appropriate rating	BI	
V	5.	Through penetration firestop system installations in walls/barriers per design documents	BI	
	Fire	Doors / Fire Windows		
v	1.	Doors/windows, frames and hardware have proper rating, properly close and latch, are labeled per design documents	BI	
V/W	2.	Doors/windows properly operate (release, close, latch) when inter-locked with fire detection and alarm system		FP
	Fire-	Proofing/Coatings		
۷	1.	Fire-proofing installed per manufacturer's instructions	BI	
V	2.	Patches and repairs to fire-proofing are installed properly	BI	
	Eleva	ators		
V/W	1.	Elevators are programmed properly for fire safety (recall floors, shut-trip, interlock with fire alarm system)		FP
	HVA	c		
v	1.	Fire/smoke dampers and duct smoke detectors are installed per design documents	BI	
V/W	2.	HVAC fan shutdown upon duct smoke detector activation and/or other control requirement via fire detection and alarm system		FP
v/w	3.	Smoke damper controls function per design documents, inter-locked with fire alarm system		FP
W	4.	Proper setting (fusible link temp) and operation of fire dampers		FP
	Eme	rgency Lighting/EXIT Signage		
V	1.	Installation in accordance with design documents (configuration with lighting, mounting, locations)	BI	
V/W	2.	Satisfactory testing/commissioning	STUP	FP
		Portable fire extinguishers		
N/		Installation/placement and appropriateness with hazards in accordance with design documents		
V	1.	During installation:	BI	
		At final:		FP

Jason Kemp (FP)	Tim Donovan (ES-FE)	Felix Sandoval (CEI OSHISH)
	Determination	: Unclassified
	Jason Kemp (FP)	