





1. PLACE 1/2" WIDE PREMOULDED EXPANSION JOINT FILLER MATERIAL AT INTERVALS NOT TO EXCEED 3 CONTROL JOINTS.
2. PREMOULDED EXPANSION JOINT FILLER MATERIAL SHALL BE PLACED BETWEEN SIDEWALKS AND STREET CURBS AND ANY OTHER RIGID STRUCTURES.
3. CONTROL JOINTS SHALL BE PLACED IN THE SIDEWALKS TO FORM A SQUARE. JOINTS MAY BE TOOLED OR SAWED AND SHALL EXTEND AT LEAST 1/3 OF THE DEPTH OF CONCRETE.

DRAWING DEVELOPED FOR ML-3/  
ML-4 PROJECTS. FOR ML-1/  
ML-2, ADDITIONAL REQUIREMENTS  
AND QA REVIEWS ARE REQUIRED.  
(REMOVED THIS NOTE WHEN IN-  
SERTED INTO A DRAWING PACK-  
AGE).

1. WHEN EDITING DETAIL TO SUIT PROJECT, ADD JOB SPECIFIC REQUIREMENTS AND DELETE ONLY THOSE PORTIONS THAT DO NOT APPLY. TO SEEK A VARIANCE FROM APPLICABLE REQUIREMENTS, CONTACT THE ESM CML POC.
2. FOR ADDITIONAL REQUIREMENTS REFER TO THE ENGINEERING STANDARDS MANUAL CML CHAPTER.

NO.	DWG.	CASE REV.	DESCRIPTION			DATE	DESIGNER/CHECKED	APP.  	
 <b>FACILITY &amp; WASTE OPERATIONS DESIGN ENGINEERING CONSTRUCTION SERVICES</b>									
<b>ENGINEERING STANDARDS MANUAL</b>						DRAWN	SUPERVISOR		
<b>SIDEWALK</b>						DESIGN	CITIMK		
						CHECKED	CARMOND		
						DATE	B-10-01		
BLDG X			TA-X						
SUBMITTED			APPROVED FOR RELEASE						
MULTIPLE PPG: EXHIBIT NO#1			STANDARD MANAGER: TOMMY GRISH						
 LOG AMERICA INC. <small>A Division of Log American Corp.</small>						PRICE		1	
						PC AND 1/4 IN. Let Alameda, New Mexico 87504		1 of 1	
CLASSIFICATION U			REVIEWER JOHN ORLICK			DATE			
PROJECT ID			DRAWING TO			RSV		0	
<b>CHAPTER 3</b>			<b>ST-G2030-1</b>						